To whom it may concern:

As of Monday **July 1, 2024,** the City of Willard will be requiring the inspection of the following items:

## **Sewer Inspection**

 Per P2503.4 The building sewer shall be tested by insertion of a test plug at the point of connection with the public sewer and filling the building sewer with water, testing with not less than a 10-foot (3048 MM) head of water and be able to maintain such pressure for 15 minutes.

## **Plumbing Inspection**

• Per P2503.5.1 DWV systems shall be tested with a water test filled with no less than a 10-foot head above the highest fitting or an air test shall be pressurized to 5 PSI or 10 inches of mercury column (34kPa) for a period of 15 minutes.

## **Insulation Inspection**

 Per chapter 11, insulation shall be inspected to insure proper installation and compliance with adopted energy standards. The **insulation company** shall provide a certificate of proper installation. This certificate shall list the predominate R-values of insulation installed in the project. This insulation certificate shall be required prior to a certificate of occupancy. It is the responsibility of the general contractor to ensure the correct installation of materials and the proper paperwork is completed.

Thank you for your understanding.

Mike Ruesch

Director of Planning & Development City of Willard Missouri